

## Subdivisional Lines, T.5 S., R.33½ E., W. M.

Chains	
	<p>N.89°30'E. on true line bet. Secs. 22 &amp; 27.</p> <p style="text-align: right;">With same Var.</p>
22.87	<p>The Cor. to Secs. 22, 23, 26 &amp; 27.</p> <p>Land; gently rolling.</p> <p>Soil; 3rd rate.</p> <p>Heavily timbered with yellow pine.</p> <p>Dense undergrowth of pine.</p>
	<p>N. bet. Secs. 22 &amp; 23.</p> <p style="text-align: right;">Var.19°20'E.</p> <p>Over rolling ground.</p> <p>Through timber.</p>
40.00	<p>Set pine post, 3 ft. long, 3 ins. sq., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, from which</p> <p style="padding-left: 40px;">A pine, 8 ins. diam., brs. N.70°W., 27 lks. dist., marked ¼ S., B.T.</p> <p style="padding-left: 40px;">A tamarack, 12 ins. diam., brs. S.68°E., 61 lks. dist., marked ¼ S., B.T.</p>
40.70	<p>A ravine, course N.W.</p>
75.00	<p>Top of raise &amp; descend along hillside, facing N.E.</p>
80.00	<p>A pine, 10 ins. diam., which I marked</p> <p style="padding-left: 40px;">T.5 S., S.14 on N.E.</p> <p style="padding-left: 40px;">R.33½ E., S.23 on S.E.</p> <p style="padding-left: 40px;">S.22 on S.W. and</p> <p style="padding-left: 40px;">S.15 on N.W. faces, with</p> <p style="padding-left: 40px;">3 notches on S. and</p> <p style="padding-left: 40px;">2 notches on E. edges</p> <p>For Cor. to Secs. 14, 15, 22 &amp; 23, from which</p> <p style="padding-left: 40px;">A pine, 6 ins. diam., brs. N.25°E., 5 lks. dist., marked T.5 S., R.33½ E., S.14, B.T.</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., brs. N.60°W., 5 lks. dist., marked T.5 S., R.33½ E., S.15, B.T.</p> <p style="padding-left: 40px;">A tamarack, 18 ins. diam., brs. S.80°W., 17 lks. dist., marked T.5 S., R.33½ E., S.22, B.T.</p> <p style="padding-left: 40px;">A tamarack, 6 ins. diam., brs. S.10°E., 10 lks. dist., marked T.5 S., R.33½ E., S.23, B.T.</p>