

South Bdy., T 5 S R 34 E W M.

Chains	
16.00	Trail, course W.
17.50	Enter hollow, course W.
28.00	Ravine, course N.W. Ascend through dense pine.
33.00	Descend through dense pine.
40.00	Set post, $3\frac{1}{2}$ ft. long; 3 ins. sq., 18 ins. in ground, on W. side of steep hill, 100 ft. above creek, for Standard $\frac{1}{4}$ Sec. Cor., marked S C $\frac{1}{4}$ S on N.; from which <p style="margin-left: 40px;">A pine, 4 ins. diam., brs. N. 27° W., 7 lks. dist., marked S C $\frac{1}{4}$ S B T.</p> <p style="margin-left: 40px;">A pine, 6 ins. diam., brs. N. 52° E., 16 lks. dist., marked S C $\frac{1}{4}$ S B T.</p>
41.75	A stream, 5 lks. wide, course N. Ascend.
54.86	Point of rocks, ascend along N. side of canyon.
58.00	Descend.
60.15	Bottom of ravine. Ascend through open pine.
80.00	Set post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in ground, on S. side of ridge, N. side of canyon, 300 ft. below summit of Standard Cor. to Secs. 33 & 34, marked S C T 5 R 34 E on N., S. 34 on E. and S 33 on W. faces, with 3 notches on E. & W. sides; from which <p style="margin-left: 40px;">A pine, 8 ins. diam., brs. N. 63° E., 18 lks. dist., marked T 5 S R 34 E S 34 B T.</p> <p style="margin-left: 40px;">A fir, 10 ins. diam., brs. N. 45° W., 16 lks. dist., marked T 5 S R 34 E S 33 B T.</p>
	Land; high, mountainous & broken. Soil; rocky & gravelly, 4th rate. Timber; pine, fir & tamarack.
	Aug. 13, 1881.
	W. on S. Bdy. of Sec. 33. Var. 20° E.
	Ascend on N. side of canyon, through heavy pine timber.
8.25	Ravine. Ascend.
21.00	Point of rock. Descend.
25.75	Bottom of canyon, course E. Ascend thru black Pine & down timber.
40.00	Set post, $3\frac{1}{2}$ ft. long, 3 ins. sq., 18 ins. in ground, on E. side of hill, in dense black pine, for Standard $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S S C on N.; from which <p style="margin-left: 40px;">A pine, 5 ins. diam., brs. N. 72° W., 9 lks. dist., marked S C $\frac{1}{4}$ S B T.</p>