

First Standard Parallel, T 5 S R 34 E W M.
 (South Bdy., T 5 S R 34 E W M.)
 As surveyed by Jacob C. Cooper, U.S. Deputy Surveyor,
 Under Contract No. 397,
 Dated July 1, 1881.

Chains

From the Standard Cor. to T. 5 S., Rs. 34 & 35 E., which
 is a post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in ground, in
 glade, 200 ft. below summit, marked S C T 5 S on N., R
 35 E S 31 on E. and R 34 E S 36 on W. faces, with 6
 notches on N., E. and W. faces; from which

A pine, 30 ins. diam., brs. N.10°E., 190 lks. dist.,
 marked T 5 S R 35 E S 31 B T.

No other tree near.

W. on S. Bdy. of Sec. 36.

Var. 20°E.

Descend.

15.00 Spring branch, course N.W.

22.00 Descend.

28.00 Enter young pine.

30.00 Creek bottom covered with willow & young pine.

33.00 Fly creek, 10 lks. wide, course N.E.

38.00 Ascend.

40.00 Set post, $3\frac{1}{2}$ ft. long, 3 ins. sq., 18 ins. in ground, on
 point of hill, sloping S. for Standard $\frac{1}{4}$ Sec. Cor.,
 marked $\frac{1}{4}$ S S C.

A pine, 44 ins. diam., brs. N.19°W., 53 lks. dist.,
 marked S C $\frac{1}{4}$ S B.T.

Descend through heavy pine timber.

46.00 Meadow land.

49.75 Spring branch, course S.E.

55.00 Enter point of black pine timber.

60.50 Leave timber.

65.75 Spring branch, course N.E.

66.90 Fence, sheep corral, house brs. S.35°E.

71.00 Enter timber and ascend.

80.00 Set post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in ground, on E.
 slope of hill, in black pine timber for Standard Cor. to
 Secs. 35 & 36, marked

S C T 5 S R 34 E on N.

S.36 on E. and

S 35 on W. faces,