

Chains

42.60 Center of stream, 10 lks. wide, course N.E.
 43.50 Ascend through black pine.
 68.50 Old Indian trail, course W.
 77.00 Summit of mountain ridge.
 Descend through dense black pine & fir timber.
 80.00 Set post, 4½ ft. long, 4 ins. sq., 2 ft. in ground, near
 summit of high ridge, course N. & S., for Standard Cor.
 to Secs. 31 and 32, marked
 S C P 5 S R 34 E on N.
 S 32 on E.
 S 31 on W. faces, with
 5 notches on E. and
 1 notch on W. faces,
 from which
 A tamarack, 14 ins. diam., brs. N.45°E., 23 lks. dist.
 marked T 5 S R 34 E S 32 B T .
 A tamarack, 11 ins. diam., brs. N.30°W., 24 lks. dist.
 marked T 5 S R 34 E S 31 B T .
 Land; high, broken and mountainous.
 Soil; rocky & gravelly, 4th rate.
 Timber; pine, fir & tamarack.

General Description

This line runs over the main divide of the Blue Mts., running N. & S. bet. the waters of the Grande Ronde & John Day Rivers.

It is very high and mountainous, rough & broken, and is a continuous forest of fir, pine, tamarack & spruce.

On both sides of the line, pure, cold mountain streams are numerous.

Wild deer and elk abound in great numbers.

Soil is poor. Grazing below average, timber fair.

Aug. 15, 1881.

Jacob C. Cooper

U.S. Deputy Surveyor.