

Field Notes of the survey of the Guide Meridian thru Tps. 6
 Rs. 30 & 31 E.,
 As surveyed by H.J. Maxon & Jared S. Hurd,
 Under their Contract No. 50,
 Dated Feb. 24, 1860.

Chains

Commence at the N.E. Cor. of Tp. 5 N., R. 30 E.

N. bet. Secs. 31 & 36.

Var. 19° 50' E.

Descend in deep sandy canyon.

- 5.00 Juniper grove brs. W.
- 22.50 Foot of hill & ascend; canyon brs. E. & W.
- 40.00 Set post for $\frac{1}{4}$ Sec. Cor. with mound of stone.
- 69.00 Top of hill.
- 80.00 Set post for Cor. to Secs. 30, 31, 25 & 26, in mound of earth with pits, trench, etc., as per instructions. Soil; 2nd rate. Sandy & rolling. Little juniper timber.

N. bet. Secs. 25 & 30.

Var. 20 $\frac{1}{4}$ ° E.

- 40.00 Set $\frac{1}{4}$ Sec. post in mound of earth with pits, trench, etc.
- 60.00 Descend hill.
- 75.00 Foot of hill.
- 80.00 Set post for Cor. to Secs. 24, 25, 19 & 30, with mound of stone in river bottom. Soil; 2nd rate. Sandy & hilly.

N. bet. Secs. 19 & 24.

Var. 20 $\frac{1}{4}$ ° E.

- 11.50 Road to Fort Walla Walla, N.E. & S.W.
- 29.00 Intersect left bank of Columbia River, runs S. 50° W.
 Set Meander post in mound of stone. Set flag and run N. 40° E. 42.50 chs. for base & set flag No. 2, crossed river on line, flag No. 2 brs. S. 18 $\frac{1}{2}$ ° E., distance over river on line, 114.20 chs. $\frac{1}{4}$ Sec. & Sec. Cors. fall in the river.
 Soil; 1st rate. River bottom, prairie.