

Subdivisional Lines, T 6 N R 30 E W M.

Chains

Land; level valley.
 Soil; deep alluvial, 1st rate.
 Timber; willow, cottonwood, cherry & haw, skirting river
 bank.
 Undergrowth; sage, good bunchgrass.

I begin at Cor. of Secs. 19, 24, 25 & 30 on E. Bdy. of Tp.,
 heretofore described.

Thence I run
 W. bet. Secs. 24 & 25.
 Over level land.

- 2.59 A fence brs. N. & S.
- 3.35 An irrigation ditch, 3 lks. wide, course S.W.
- 6.13 An irrigation ditch, 8 lks. wide, course N.W.; enter field
- 13.68 A fence, brs. N.E. & S.W. and enter roadway.
- 15.59 Center line of main track of O.W.R. & N. R.R., brs. N.34°
 38' E. and S.34° 38' W.
- 22.99 To left bank of Columbia River.

Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for
 Meander Cor. of fracl. Secs. 24 & 25, mkd. M C on W.
 face, with 2 grooves on S. face; dig pit, 36 x 36 x 12
 ins., 8 ft. E. of stone & raise mound of earth, 4 ft.
 base, 2 ft. high, E. of Cor.

S.D. Tucker's engine house brs. N.43°26' E.

Land; level valley.
 Soil; volcanic ash, 1st rate.
 No timber.
 No undergrowth.

From the Cor. of Secs. 2, 3, 34 & 35, on S. Bdy. of Tp.,
 heretofore described.

- Thence I run
- N.0°01' W. bet. Secs. 34 & 35.
- Descend over loose, sandy soil.
- 5.00 Enter bench, brs. N.E. & S.W.