

Subdivisional Lines, T 6 N R 30 E W M.

Chains	
	Descend over loose slide rock.
6.00	Enter level valley, course N.E. & S.W.
10.14	Center line of main track of O.W.R. & N. R.R., brs. N.53° 31' E. & S.53° 31' W.
12.00	Right- of -way fence parallel to railroad and enter field.
24.24	To left bank of Columbia River.
	Set basalt stone, 18 x 12 x 6 ins., 12 ins. in ground, for Meander Cor. for fracl. Secs. 26 & 35, mkd. M C on W. face, with 1 groove on S. face; from which A willow, 6 ins. diam., brs. S.24° E., 20 lks. dist., mkd. T 6 N R 30 E S 35 M C B T. AA willow, 8 ins. diam., brs. N.76°30'E., 46 lks. dist., mkd. T 6 N R 30 E S 26 M C B T.
	Land; level valley, except first 6 chs. Mtns. Soil; deep, sandy loam , 1st & 2nd rates. No timber, except a few willows skirting river bank. No undergrowth.
	From the Cor. of Secs. 3, 4, 33 & 34 on S. Bdy. of Tp., h heretofore described I run N.0°02' W. bet. Secs. 33 & 34. Descend over rock bluffs.
3.28	Foot of bluff in railroad cut, 360 ft. below Sec. Cor. Cut a cross in face of bluff on line.
3.81	South rail of main track of O.W.R. & N.R.R., brs. N.62°54' E. and S.62°54' W.
4.44	To left bank of Columbia River. Set basalt stone, 30 x 18 x 5 ins., 22 ins. in ground, for Meander Cor. of fracl. Secs. 33 & 34, mkd. M C on N. face with 3 grooves on E. face; deposit pint of charcoal un- der stone; dig pit, 36 x 36 x 12 ins., 8 ft. S. of stone and raise mound of earth, 3½ ft. base, 1½ ft. high, S. of Cor.
	Land; mountainous. Soil; rocky, 4th rate. No timber. Undergrowth; willow & service skirting river bank.