

Meanders, Tp. 6 N., R. 30 E., W.M.
As surveyed by the same U.S. Transitman,
Under the same Instructions & Date.

MEANDERS OF LEFT BANK OF COLUMBIA RIVER, DOWN STREAM.

I commence at the Meander Cor. of fracl. Secs. 19 & 24, on
E. Bdy. of Tp., heretofore described.

Thence I run with meanders in Sec. 24.

Along dirt bank, 10 ft. high, with wide gravel beach.

S. 39° 23' W. 36.23 chs. At 18.53 chs. S.D. Tucker's
engine house bears S. 45° E.,
75 lks. distant.
At 21.80 chs. mouth of
ravine, 75 lks. wide, course
N.W.
To Meander Cor. of fracl.
Secs. 24 & 25.

Land; level.

Soil; sandy loam, 1st rate.

No timber.

No undergrowth.

Thence in Sec. 25.

S. 48° 30' W. 11.20 chs.
S. 34° W. 11.90 chs.
S. 18° W. 7.70 chs. At 2.28 chs. a fence bears
East, and a road bears S.
26° 30' E.
S. 26° 30' E. 2.90 chs. Johnson's cabin bears
S. 77° E., 10 chs. distant
S. 8° W. 7.50 chs. At end of course, edge of
railroad embankment 12 ft.
high.
S. 47° 30' W. 4.70 chs. Along railroad embankment.
S. 63° 15' W. 27.80 chs.
S. 37° W. 5.00 chs. At end of course, fence
bears South.
S. 80° W. 10.00 chs. At fringe of cottonwood
and willow timber.
To Meander Cor. of fracl.
Secs. 25 & 26.

Land; level.

Soil; sandy loam, 1st rate.

Timber; cottonwood & willow.

Undergrowth; sage.

Thence in Sec. 26.

S. 70° W. 4.00 chs.