

Exterior Lines, T 6 N R 31 E W M.

Chains	
39.00	<p>Set post Closing Cor. on N. Bdy. of State, 8.08 chs. W. of 5th Mile post, for Secs. 13 & 18.</p> <p>Land; broken.</p> <p>Grass; good.</p> <p>Soil; 2nd rate.</p>
<p>Subdivisional Lines, T 6 N R 31 E W M., As surveyed by Nicholas O. Walden, U.S. Dept. Surveyor, Under Contract No. 209, Date July 6, 1874.</p>	
<p>Begin at the Cor. of Secs. 35 & 36 in S. Bdy. of Tp. & run N. bet. Secs. 35 & 36.</p>	
12.00	Juniper Canyon, course W.
40.00	<p>Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.</p>
80.00	<p>Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 25, 26, 35 & 36.</p> <p>Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.</p> <p>Land; hilly.</p> <p>Soil; good.</p>
<p>E. on random line bet. Secs. 25 & 36.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.00	<p>Intersect E. Bdy. of Tp., 200 lks. S. of Cor.</p> <p>This Close not being within the limits required by instructions, I retrace this line & the line bet. Secs. 25 & 36, and find no error.</p> <p>I, therefore, begin at the Cor. to Tps. 5 & 6 N., Rs. 31 & 32 E. and run thence</p>
<p>N. on blank line along E. Bdy. of Sec. 36, T 6 N R 31 E.</p>	
40.46	The $\frac{1}{4}$ Sec. Cor.
81.44	The Cor. to Secs. 25 & 26.
<p>Note:</p> <p>The S. Bdy. of Sec. 36 in this Tp., is 80.86 chs. in length and has a bearing to the S. of W., 58 lks. (See field</p>	