

Subdivisional Lines, T 6 N R 31 E W M.

Chains	
	N. bet. Secs. 26 & 27. Var. 21°30' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
53.00	Ravine, course S.W.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 22, 23, 26 & 27. Drove pine stake, 2 ft. long, 2 ins. sq. in S.E. pit. Land; hilly. Soil; good.
	E. on random line bet. Secs. 23 & 26.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N. & S. line, 10 lks. S. of Cor. S. 89°56' W. on true line.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	The Cor. Land; gently rolling. Soil; 1st rate.
	N. bet. Secs. 22 & 23. Var. 21°30' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound, of earth, with pits, etc., as per instructions, for Cor. to Secs. 14, 15, 22 & 23. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate.
	E. on random line bet. Secs. 14 & 23.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.75	Intersect N. & S. line, 35 lks. S. of the Cor.