

## Subdivisional Lines, T 6 N R 32 E W M.

Chains	
	N. bet. Secs. 27 & 28.
	Var. 22°00' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 21, 22, 27 & 28. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 1st rate. Grass; good.
	Nov. 21st, 1874.
	E. on random line bet. Secs. 22 & 27.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
81.00	Intersect N. & S. line at Cor. W. on true line.
40.50	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
81.00	The Cor. Land; rolling. Soil; good. Grass; good.
	N. bet. Secs. 21 & 22.
	Var. 21°30' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Set basalt stone, 15 x 8 x 6, 8 ins. in ground, for Cor. to Secs. 15, 16, 21 & 22. Land; gently rolling. Soil; good.
	E. on random line bet. Secs. 15 & 22.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.