

Subdivisional Lines, T 6 N R 32 E W M.

Chains	
	E. on random line bet. Sees. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.70	Intersect N. & S. line at Cor.
	W. on true line.
40.35	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.70	The Cor. Land; rolling. Soil; 1st rate. Grass; good.
	W. on random line bet. Sees. 30 & 31.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.83	Intersect W. Bdy. of Tp., 35 lks. S. of Cor. S. 89° 45' E. on true line.
40.83	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.83	The Cor. Land; rolling. Soil; good. Grass; good.
	N. bet. Sees. 29 & 30. Var. 21° 30' E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Sees. 19, 20, 29 & 30. Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; good. Grass; good.