

Subdivisional Lines, T 6 N R 34 E W M.

Chains	N. bet. Sees. 25 & 26.	Var. 21° E.
.65	Road, course E. & W.	
9.15	Dry creek, course N.W.	
34.40	Spring branch, 7 lks. wide, course N.W.	
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.	
80.00	Set post Cor. for Sees. 23, 24, 25 & 26. Drove charred stake; dug pits & raised mound, as per instructions.	
	Land; gently rolling.	
	Grass; good.	
	Soil; good 2nd rate.	
	E. on random bet. Sees. 24 & 25.	
5.00	Creek, course N.W.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	
79.63	Intersect E. Tp. line, 59 lks. S. of post, from which I run	
	S. 89° 35' W. on true line.	
39.81	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	
79.63	To post Cor.	
	Land; gently rolling.	
	Grass; good.	
	Soil; 2nd rate.	
	N. bet. Sees. 23 & 24.	Var. 21° E.
8.10	Spring branch, course N.W.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	
57.00	Road, course W.	
80.00	Set post Cor. for Sees. 13, 14, 23 & 24. Drove charred stake; dug pits & raised mound, as per instructions.	