

## Subdivisional Lines, T 6 N R 33 E W M.

## Chains

for fractional Secs. 14 & 15. Drove charred stake; dug pits & raised mound, as per instructions.

Land; gently rolling.

Soil; good 2nd rate.

N. bet. Secs. 33 & 34.

Var. 21° E.

40.00 Set  $\frac{1}{4}$  Sec. post Cor.

80.00 Set post Cor. for Secs. 27, 28, 33 & 34. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Grass; good.

Soil; 2nd rate.

E. on random bet. Secs. 27 & 34.

40.00 Set temp.  $\frac{1}{4}$  Secs. post.

79.50 Intersect N. & S. line, 47 lks. N. of post, from which, I run

N. 89° 40' W. on true line.

39.75 Set  $\frac{1}{4}$  Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

79.50 To post Cor.

Land; broken.

Soil; 2nd rate.

N. bet. Secs. 27 & 28.

Var. 21° E.

40.00 Set  $\frac{1}{4}$  Sec. post Cor. Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 21, 22, 27 & 28. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Soil; 2nd rate.