

Subdivisional Lines, T 6 N R 35 E W M.

Chains	stake; dug pits & raised mound, as per instructions. Land; rolling. Soil; 2nd rate.
	N. bet. Secs. 34 & 35. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 26, 27, 34 & 35. Drove charred stake; dug pits & raised mound, of stone, as per instructions. Land; level & quite stony. Grass; good.
	E. on random bet. Secs. 26 & 35.
20.00	Creek, 20 lks. wide, course N.
39.00	" " " " " "
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
58.40	Creek, 30 lks. wide, course N.
79.87	Intersect N. & S. line, 20 lks. N. of post, from which, I run N. 89° 51' W. on true line.
39.93	Set $\frac{1}{4}$ Sec. post. Drove charred stake & raised mound, as per instructions.
79.87	To post Cor. Land; level. Soil; gravelly.
	N. bet. Secs. 26 & 27. Var. 21° E.
34.00	Creek, 15 lks. wide, course N.W.
40.00	Set $\frac{1}{4}$ Sec. Cor. post. Drove charred stake; dug pits & raised mound, as per instructions, and from which an alder brs. S. 36° W., 76 lks.