

Subdivisional Lines, T 6 N R 35 E W M.

Chains

80.00 Set post Cor. for Secs. 21, 22, 27 & 28. Drove charred stake; dug pits & raised mound, as per instructions.
 Land; level.
 Soil; 2nd rate.

E. on random bet. Secs. 22 & 27.

9.75 Road, course N.W.
 21.20 Creek, 10 lks. wide, course N.
 29.00 Road, course N.W.
 30.00 Enter field.
 40.00 Set $\frac{1}{4}$ Sec. temp. Cor.
 60.17 Creek, 10 lks. wide, course N.W.
 73.25 " " " " " N.
 79.00 Creek, 40 lks. " " "
 79.55 Intersect N. & S. line, 10 lks. N. of post, from which, I run
 N.89°56' W. on true line.
 39.77 Set $\frac{1}{4}$ Sec. post Cor. Drove charred stake; dug pits & raised mound, as per instructions.
 79.55 To post Cor.
 Land; level in field.
 Soil; 1st rate., W. 2nd rate.

N. bet. Secs. 21 & 22.

Var.21°E.

23.50 Spring branch, 4 lks. wide, course N.W.
 40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound as per instructions.
 58.50 Branch, 4 lks. wide, course N.W.
 60.40 Road, course N.W.
 80.00 Set post Cor. for Secs. 14, 15, 21 & 22. Drove charred stake; dug pits & raised mound, as per instructions.
 Land; level.
 Soil; 2nd rate.