

## Exterior Lines, T 6 N R 36 E W M.

## Chains

- 40.00 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
- 52.00 Intersect State Line, 16.25 W. of Mile post No. 35.  
Set post for Cor. to fractional Sees. 13 & 18. Drove charred stake; dug pits & raised mound, as per instruct.

Subdivisional Lines, T 6 N R 36 E W M.  
As surveyed by the same U.S. Deputy Surveyors,  
Under the same Contract and date.

N. bet. Sees. 35 & 36.

Var. 21° E.

- 40.00 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
- 80.00 Set post Cor. for Sees. 25, 26, 35 & 36. Drove charred stake; dug pits & raised mound, as per instructions.  
Land; rolling.  
Grass; good.  
Soil; 2nd rate.

E. on random bet. Sees. 25 & 36.

- 40.00 Set temp.  $\frac{1}{4}$  Sec. post.
- 79.75 Intersect N. & S. Tp. line, 29 lks. N. of post, from which  
I run  
N. 89° 48' W. on true line.
- 39.87 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised mound, as per instructions. Post set on side hill, sloping to the E.
- 79.75 To post Cor.  
Land; rolling.  
Grass; good.  
Soil; 2nd rate.

N. bet. Sees. 25 & 26.

Var. 21° E.

- 40.00 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised