

## Subdivisional Lines, T 6 N R 36 E W M.

## Chains

mound, as per instructions.

- 80.00 Set post Cor. for Secs. 22, 23, 26 & 27, on level. Drove charred stake; dug pits & raised mound, as per instruct.  
Land; gently rolling.  
Grass; good.  
Soil; 2nd rate.

E. on random bet. Secs. 23 & 26.

- 40.00 Set temp.  $\frac{1}{4}$  Sec. post.  
79.93 Intersect N. & S. Tp. line at post, from which, I run W. on true line.  
39.96 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.  
79.93 To post Cor.  
Land; rolling.  
Grass; good.  
Soil; 2nd rate.

N. bet. Secs. 22 & 23.

Var. 21° E.

- 40.00 Set  $\frac{1}{4}$  Sec. post, on level. Drove charred stake; dug pits & raised mound, as per instructions.  
80.00 Set post Cor. for Secs. 14, 15, 22 & 23. Drove charred stake; dug pits & raised mound, as per instructions.  
Land; gently rolling.  
Grass; good.  
Soil; 2nd rate.

E. on random bet. Secs. 14 & 23.

- 40.00 Set temp.  $\frac{1}{4}$  Sec. post.  
80.19 Intersect N. & S. Tp. line, 40 lks. N. of post, from which, I run N. 89° 43' W. on true line.  
40.09 Set  $\frac{1}{4}$  Sec. post. Drove charred stake; dug pits & raised