

Subdivisional Lines, T 6 N R 36 E W M.

Chains	
	N. bet. Secs. 20 & 21.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 16, 17, 20 & 21. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Grass; good. Soil; 2nd rate.
40.00	E. on random bet. Secs. 16 & 21. Set temp. $\frac{1}{4}$ Sec. post.
79.68	Intersect N. & S. line, at post, from which, I run W. on true line.
39.84	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
42.50	Road; course W. of N.
79.68	To post Cor. Land; rolling gently. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 16 & 17.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
53.00	Intersect State Bdy. Line, 17 chs. W. of Mile post No. 31. Set post Cor. for fractional Secs. 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Grass; good. Soil; 2nd rate.