

Subdivisional Lines, T 6 N R 36 E W M.

Chains	N. bet. Secs. 19 & 20.
	Var. 21° E.
40.00	Set $\frac{1}{2}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 17, 18, 19 & 20. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; gently rolling.
	Grass; good.
	Soil; good 2nd rate.
	E. on random bet. Secs. 17 & 20.
40.00	Set temp. $\frac{1}{2}$ Sec. post.
80.19	Intersect N. & S. line, 30 lks. S. of post, from which, I run
	S. 89° 47' W. on true line.
40.09	Set $\frac{1}{2}$ Sec. post. Dug pits & raised mound, as per instructions.
80.19	To post Cor.
	Land; rolling gently.
	Grass; good.
	Soil; good 2nd rate.
	W. on random bet. Secs. 18 & 19.
40.00	Set temp. $\frac{1}{2}$ Sec. post.
79.94	Intersect N. & S. T er line at post, from which, I run
	E. on true line.
39.94	Set $\frac{1}{2}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
79.94	To post Cor.
	Land; rolling gently.
	Grass; good.
	Soil; 2nd rate.
	N. bet. Secs. 17 & 18.
	Var. 21° E.
40.00	Set $\frac{1}{2}$ Sec. post. Drove charred stake; dug pits & raised