

Subdivisional Lines, T 6 N R 37 E W M.

Chains	
80.00	Set stone in mound, 7 x 12 x 10, for Cor. to Secs. 22, 23, 26 & 27. Land; mountainous. Timber; fir & pine.
	E. on random line bet. Secs. 23 & 26.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.20	Intersect N. & S. line, 60 lks. S. of the Cor., for Secs. 23, 24, 25 & 26, from which, Cor. run S. 89° 34' W. on true line bet. Secs. 23 & 26.
12.90	Timber road, N.W. & S.E.
37.80	Timber road, N.W. & S.E.
40.10	Set rock, 6 x 10 x 16, mound of rock, with pits for $\frac{1}{4}$ Sec. Cor.
80.20	The Cor. for Secs. 22, 23, 26 & 27. Land; rocky. Timber; fir & pine. Oct. 19, 1872.
	N. bet. Secs. 22 & 23. Var. 21 $\frac{1}{2}$ ° E.
27.90	Timber road, N. 50° E. Ascend.
35.00	Summit Pike's Peak ridge, 800 ft.; descend.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., edge of timber. A red fir, 20 ins. diam., brs. N. 20° E., 44 lks. dist. A " " 12 " " " N. 33° W., 92 " "
60.00	Bottom of dry gulch, 700 ft.; ascend; leave timber.
80.00	Set rock, 14 x 16 x 20, mound of rock, for Cor. to Secs. 14, 15, 22 & 23. Land; rough. Timber; pine, fir & tamarack.
	E. on random line bet. Secs. 14 & 23.