

Subdivisional Lines, T 6 N R 37 E W M.

Chains	<p>12.30 Cross creek, 20 lks. wide, runs W.</p> <p>16.00 Cross creek, 2 lks. wide, runs W.</p> <p>20.25 Cross fence.</p> <p>39.50 Set stone, 6 x 8 x 10, mound & pits, for $\frac{1}{4}$ Sec. Cor.</p> <p>45.00 Mr. Marchous's house brs. S. 4 lks. dist.</p> <p>60.06 Cross fence, enter field.</p> <p>61.50 Cross fence, leave field.</p> <p>74.35 Irrigating ditch.</p> <p>77.50 Creek, 2 lks. wide.</p> <p>79.50 The Cor. for Secs. 17, 18, 19 & 20.</p> <p>Soil; 1st rate.</p> <p style="text-align: right;">Oct. 24, 1872.</p> <hr/> <p>N. bet. Secs. 18 & 17.</p> <p style="text-align: right;">Var. $20\frac{1}{4}^{\circ}$ E.</p> <p>.60 Cliff, 12 ft. Descend, enter bottom.</p> <p>3.30 Creek flows W., 15 lks. wide.</p> <p>10.00 Enter lane.</p> <p>40.00 Set stone, 6 x 12 x 18 for $\frac{1}{4}$ Sec. Cor.</p> <p>52.20 Intersect N. Bdy. of State, 16.33 chs. W. 36 M. post.</p> <p>Set stone, 5 x 8 x 13 for Cor. to fractional Secs. 17 & 18.</p> <p>Land; rolling; 1st rate.</p> <hr/> <p style="text-align: center;">General Description.</p> <p>This Tp. is much cut with deep canyons, which br. N.W. & S.E. The soil on the ridges is generally good. Eastern portion is high up on the Blue Mts. The western is more level, being nearer the ft. of the Mts.</p> <p>The ravines are not so deep (or many)?. Excellent soil. Is being rapidly settled. The timber consists of fir, tamarack, pine, spruce, birch, alder, cottonwood and willow are in the western portion of Tp.</p> <p style="text-align: right;">Completed Oct. 25, 1872.</p>
--------	---