

East Bdy. of T 6 N R-38 E., W.M.  
 As surveyed by George Williams, U.S. Deputy Surveyor  
 Under Contract No. 176, Dated July 20, 1872.

Chains		Feet
	N. on E. Bdy. of Sec. 36 Var. 24° E.	
5.00	Descend	
40.00	Set stone, 22 x 14 x 18 ins. in mound of earth and stone on side hill, face N.W.	
43.00	Bottom of gulch, falls N. 83° W.	
56.00	Ridge, falls W. 300 ft.	
80.00	Set post on side hill faces NW. for Cor. to Secs. 25, 30, 31, & 36. A spruce tree, 27 ins. diam., brs. N. 27° E., 78 lks. A pine tree, 41 ins. diam. brs. S. 24° W., 49 lks. No other trees convenient. Land; mountainous Timber; pine, fir, tamarack and spruce, scattering & scrubby.	
<hr/>		
	N. on E. Bdy. of Sec. 25. Var. 21 3/4° E.	
	Descending	
40.00	Set post for 1/4 Sec. Cor. from which A fir, 10 ins. diam., brs. N. 84° W., 75 lks. dist. A fir, 11 ins. diam. brs. S. 59° E., 21 lks. dist.	
80.00	Set post, & marked stone in mound of stone on side hill faces N.E. A tamarack, 13 ins. diam. brs. N. 50° W., 190 lks. A fir, 10 ins. diam. brs. N. 18° E., 78 lks. dist. A fir, 7 ins. diam. brs. S. 40° E., 91 lks. dist. Land; mountainous Timber; pine, fir, tamarack and spruce	
<hr/>		
	N. on E. Bdy. of Sec. 24 Var. 21° E.	
21.00	Bottom of Gulch and creek, 7 lks. wide, fall N.W. Ascend	
40.00	Set post for 1/4 Sec. Cor., from which A fir, 8 ins. diam., brs. N. 10° E., 71 lks. dist. A fir, 11 ins. diam. brs. S. 30° W., 42 lks. dist.	