

Subdivisional Lines of T 6 N R 38 E., W.M.

Chains		Feet
80.28	Intersect E. Bdy. of Tp. 57 lks. W. of the Cor. for Secs. 19, 24, 25 & 30, from which Cor. I run on a true line. N. 89° 36' W. bet. Secs. 24 and 25	
40.14	Set post $\frac{1}{4}$ Sec. Cor. from which A pine, 10 ins. diam. brs. N. 10° E. 75 lks. dist. A fir, 7 ins. diam. brs. S. 35° W., 122 lks. dist.	
46.28	Spring branch, 1 lks wide, falls N. Ascend	
67.28	Summit of ridge, brs. N. and S. Descend	
80.28	Intersect Cor. fo Secs. 23, 24, 26 & 25. Land; mountainous Timber; pine and fir.	
	N. bet. Secs. 23 & 24 Var. 21 $\frac{1}{4}$ ° E.	
	Descend	
29.00	Creek, 12 lks. wide, falls NW.	
31.50	Ascend, leave timber	
40.00	Set post and mark stone in mound of rock and earth with pits for $\frac{1}{4}$ Sec. Cor.	
58.50	Summit of ridge, 400 ft. descend	
80.00	Set post on steep hill side, face W. A white fir, 12 ins. diam. brs. N. 50° E., 200 lks. dist., A Red fir, 14 ins. diam. brs. N. 20° W., 71 lks. dist., for the cor. of Secs. 13, 14, 23 & 24.	
	Land; rough and rocky Timber, fir, pine and tamarack Undergrowth, the same, with willow and vine maple	
	E. on a random line bet. Secs. 13 & 24	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.60	Intersect E. Bdy. of Tp. 30 lks. N. of the Cor. of Secs. 13, 18, 19 & 24, from which cor. I run on a true line bet. Secs. 13 & 24, N. 89° 47' W.	
66.60	Gulch, falls N. 30° W., 100 ft., ascend	
11.35	Summit of steep ridge, 400 ft. falls N.W.	