

Exterior Lines of T. 6 S., R. 30 E., W.M.

Chains		Feet
	Exterior Bdy. of T. 6 S., R. 30 E., W.M. As surveyed by Henry Meldrom, U.S. Deputy Surveyor, Under same contract, and date.	
	N. on E. Bdy. Sec. 36. Var. 23° 10' E.	
	Descend hill from Cor., brs. N.E.	
40.00	Set a basalt stone, 12 x 12 x 6 in a mound of stone for ¼ Sec. Cor.	
80.00	Set a basalt stone, 18 x 15 x 6 in a mound of stone for Cor to Secs. 25, 30, 31 & 36.	
	Land; hilly Soil; 2nd rate. Pine and fir timber.	
	N. on E. Bdy. of Sec. 25 Var. 23° E.	
8.90	N. fork of John Days river, runs S.W. Set flag and cross to apposite bank, on line where flag brs. due S., measure base, W. 360 lks. from which pt. the flag brs. S. 45° E., the distance across river is therefore 360 lks.	
13.00	Ascend hill, brs. E. and W.	
29.00	Creek, 4 lks. wide, runs. S.W.	
40.00	Set a basalt stone, 16 x 12 x 10 ins. in a mound of stone for ¼ Sec. Cor., from which, A Pine, 24 ins. in diam. brs. S. 23° W., 180 lks. dist.	
80.00	Set a basalt stone, 18 x 14 x 10 in a mound of stone for Cor. to Secs. 19, 24, 25 & 30.	
	Land; hilly Soil; 2nd and 3rd rate. Scattering pine and fir timber. Undergrowth of greasewood and laural.	
	N. on E. Bdy. Sec. 24 Var. 18° 15' E.	
5.00	Ravine, course S., 10° E.	