

Chains	Feet
	10, 15 & 16, from which Cor. I run
	S. 88° 36' W. on a true line bet. Secs. 9 & 16
14.23	Top of hill, brs. N.W. and S.E.
28.73	Dry ravine, runs S.E.
39.61	Set a basalt stone, 14 x 10 x 8, in mound of stone, for ¼ Sec. Cor.
44.63	Dry ravine, runs. S.E.
61.43	Dry ravine, course S.E.
74.63	Dry ravine, course S.E.
79.23	To Cor. to Secs. 8, 9, 16 & 17
	Land; W. 65 Chs. rolling, remainder hilly
	Soil; 2nd rate.
	Heavy pine and tamarack on W. 5 Chs and E. 5 Chs.
	Scattering pine on remainder.
	July 2, 1881
<hr/>	
	N. bet. Secs. 8 & 9
	Var. 20° 15' E.
.50	Dry ravine, course E.
40.00	Set a Y. pine post for ¼ Sec. Cor., from which
	A Y. pine, 28 ins. diam. brs. N. 12° E., 64 lks. dist.
	A Y. Pine, 36 ins. diam. brs. N. 23° W., 58 lks. dist.
61.50	Descend hill, brs. N.E. and S.W.
71.50	Creek, 3 lks. wide in ravine, runs, N.E.
80.00	Set a basalt stone, 18 x 8 x 6, and mound of stone for Cor. to Secs. 4, 5, 8 & 9.
	Land; S. 61.50 Chs. rolling, remainder hilly
	Soil; 2nd rate.
	Heavy pine and fir timber on S. 75 Chs. and dense young fir, pine and greasewood. Scattering pine on remainder.
<hr/>	
	E. on a random line bet. 4 & 9
40.00	Set a temp. ¼ Sec. Cor.
79.55	Intersect N. and S. line, 183 lks. S. of Cor. to Secs. 3, 4, 9 & 10, from which Cor. I run