

## Exterior Lines, T 7 S R 32 E W M.

Chains	
	<p>Land; hillside, general slope to N.            Soil; 2nd rate.            Heavy piñe, fir &amp; tamarack timber.            Undergrowth; fir, pine, tamarack &amp; mountain laurel.</p>
	<p>N.89°47'E. on true line on N. Bdy. of Sec.4.            Var.20°10'E.</p>
35.00	Descend hill, brs. N. & S.
40.00	<p>Set fir post for <math>\frac{1}{4}</math> Sec. Cor., from which            A fir, 6 ins. diam., brs. N.42°W., 21 lks. dist.            A yellow pine, 28 ins. diam., brs. S.39°W., 47 lks. dist.</p>
41.60	<p>Ravine &amp; foot of hill brs. N. &amp; S.            Ascend hill from ravine, brs. N. &amp; S.</p>
59.00	Top of hill, brs. N. & S.
66.50	Descend hill, brs. N.W. & S.E.
80.00	<p>Set yellow pine post, for Cor. to Secs. 3, 4, 33 &amp; 34, from            which            A yellow pine, 20 ins. diam., brs. N.52°E., 31 lks. dist.            A yellow pine, 24 ins. diam., brs. N.63°W., 100 lks. dist.            A yellow pine, 34 ins. diam., brs. S.38°W., 19 lks. dist.            A fir, 24 ins. diam., brs. S.63°E., 36 lks. dist.</p>
	<p>Land; hilly.            Soil; 2nd rate.            Heavy pine, fir &amp; tamarack.            Dense undergrowth of young fir &amp; pine &amp; mountain laurel.</p>
	<p>N.89°47' E. on N. Bdy. of Sec.3            Var.19°30' E.</p>
13.30	Ravine, course N.E.
17.40	Ravine, course N.
28.50	<p>Creek, 5 lks. wide, runs N.            Foot of hill, brs. N. &amp; S.            Ascend from creek.</p>
40.00	<p>Set fir post, for <math>\frac{1}{4}</math> Sec. Cor.            A yellow pine, 16 ins. diam., brs. N.47°W., 29 lks. dist.            A yellow pine, 12 ins. diam., brs. S.43°W., 42 lks. dist.</p>