

Exterior Lines, T 6 S R 32 E W M.

Chains

- 25.10 Brook, 3 lks. wide, course S.W.
- 40.00 A point, 200 ft. above Tp. Cor.  
 Set post, 3 ft. long, 3 ins. sq., with marked stone, 12 ins. in ground, for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  S on W. face, from which,  
 A pine, 30 ins. diam., brs. S.37°W., 108 lks. dist., marked  $\frac{1}{4}$  S B T.  
 A pine, 30 ins. diam., brs. N.18°E., 124 lks. dist., marked  $\frac{1}{4}$  S B T.
- 73.00 Ascend abruptly.
- 79.00 Trail, course E. & W.
- 80.00 Set basalt stone, 18 x 10 x 5 ins., 12 ins. in ground, for Cor. to Secs. 25, 30, 31 & 36, marked with 5 notches on N. and 1 notch on S. edges, from which  
 A pine, 10 ins. diam., brs. N.36°E., 72 lks. dist., marked T 6 S R 33 E S 30 B T.  
 A pine, 40 ins. diam., brs. S.48°E., 54 lks. dist., marked T 6 S R 33 E S 31 B T.  
 A pine, 30 ins. diam., brs. S.51°W., 81 lks. dist., marked T 6 S R 32 E S 36 B T.  
 A pine, 18 ins. diam., brs. N.19°W., 70 lks. dist., marked T 6 S R 32 E S 25 B T.
- Land; mountainous.  
 Soil; 2nd rate.  
 Densely covered with forests of pine timber, 80 chs.

N. bet. Secs. 25 & 30.

Var.19°45'E.

- 10.00 Top of ascent.
- 15.00 Descend abruptly.
- 30.40 Spring branch at foot of hill, course W.  
 Ascend gently from branch.
- 40.00 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  S on W. face, from which  
 A fir, 24 ins. diam., brs. S.58°E., 19 lks. dist., marked  $\frac{1}{4}$  S B T.