

Exterior Lines, T 6 S R 32 E W M.

Chains.	
	<p>A fir, 10 ins. diam., brs. N.47°W., 238 lks. dist., marked T 6 S R 32 E S 12, B T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, fir, tamarack and spruce timber.</p> <p>Occasional thickets of balm, small tamarack & pine brush.</p> <p style="text-align: right;">June 3rd 1883.</p>
	<p>N. bet. Secs. 7 & 12.</p> <p style="text-align: right;">Var. 20°30'E.</p> <p>Over rolling ground and dense timber.</p>
23.60	Wagon road, course E. & W.
40.00	<p>Set basalt stone, 24 x 13 x 9 ins., 18 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which</p> <p>A fir, 10 ins. diam., brs. N.56°W., 5 lks. dist., marked $\frac{1}{4}$ S B T.</p> <p>A fir, 18 ins. diam., brs. S.42°E., 22 lks. dist., marked $\frac{1}{4}$ S B T.</p>
80.00	<p>Set basalt stone, 26 x 10 x 3 ins., 9 ins. in ground, for Cor. to Secs. 1, 6, 7 & 12, marked with 1 notch on S. and 5 notches on S. edges, from which</p> <p>A pine, 18 ins. diam., brs. N.21°E., 103 lks. dist., marked T 6 S R 33 E S 6 B T.</p> <p>A pine, 30 ins. diam., brs. S.59°E., 354 lks. dist., marked T 6 S R 33 E S 7 B T.</p> <p>A pine, 30 ins. diam., brs. S.42°W., 308 lks. dist., marked T 6 S R 32 E S 12 B T.</p> <p>A pine, 30 ins. diam., brs. N.52°W., 187 lks. dist., marked T 6 S R 32 E S 1 B T.</p> <p>Land; rolling.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, fir & tamarack and spruce timber, partly deadened by fir, 80 chs.</p> <p><u>Thick undergrowth of balm, pine, tamarack & fir, 80 chs.</u></p>