

Subdivisional Lines, T 6 S R 32 E W M.

| Chains | |
|--------|---|
| 15.00 | Cross ravine, course S.20°W and Ascend hill, facing SE. |
| 40.00 | Set basalt stone, 16 x 10 x 8 ins., 10 ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face, from which A fir, 10 ins. diam., brs. S.32°E., 50 lks. dist., marked ¼ S B T. A fir, 12 ins. diam., brs. N.44°W., 51 lks. dist., marked ¼ S B T. |
| 43.50 | Wagon road, course E. & W. on top of hill. |
| 68.25 | Creek, 4 lks. wide, course W. |
| 80.00 | Set basalt stone, 20 x 8 x 8 ins., 15 ins. in ground, for Cor. to Secs. 10, 11, 14 & 15, marked with 4 notches on S. and 2 notches on E. edges, from which A pine, 24 ins. diam., brs. N.71°E., 31 lks. dist., marked T 6 S R 32 E S 11 B T. A pine, 30 ins. diam., brs. S.15°E., 61 lks. dist., marked T 6 S R 32 E S 14 B T. A pine, 30 ins. diam., brs. S.59°W., 65 lks. dist., marked T 6 S R 32 E S 15 B T. A pine, 20 ins. diam., brs. N.30°W., 111 lks. dist., marked T 6 S R 32 E S 10 B T. |
| | Land; mountainous. Soil; 2nd rate. Densely covered with forests of pine, fir & tamarack timber, 80 chs. Thick undergrowth of small pine, fir & balm, 80 chs. |
| | E. on random line bet. Secs. 11 & 14. Var. 19°10'E. |
| | Descend gently. |
| 16.00 | Foot of descent, brook, 4 lks. wide, course S.W. |
| 40.00 | Set temp. ¼ Sec. Cor. |
| 51.50 | Brook, 3 lks. wide, course N.60°W. Thence gently ascend along hillside, facing S.W. |
| 80.40 | Intersect N. & S. line at 8 lks. N. of Cor. to Secs. 11, |