

Subdivisional Lines, T 6 S R 32 E W M.

Chains	
	N. bet. Secs. 15 & 16.
	Var. 20°E.
	Ascending gradually.
34.50	Wagon road, course N.E. & S.W.
36.00	Top of hill, 180 ft. above Sec. Cor.
40.00	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which A pine, 36 ins. diam., brs. S. 31°E., 17 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 30 ins. diam., brs. N. 63°W., 29 lks. dist., marked $\frac{1}{4}$ S B.T.
52.00	Ravine, course W.
71.75	" " "
80.00	Set basalt stone, 16 x 12 x 9 ins., 10 ins. in ground, for Cor. to Secs. 9, 10, 15 & 16, marked with 4 notches on S. and 3 notches on E. edges, from which A pine, 18 ins. diam., brs. N. 29°E., 32 lks. dist., marked T 6 S R 32 E S 10 B T. A pine, 30 ins. diam., brs. S. 75°E., 52 lks. dist., marked T 6 S R 32 E S 15 B T. A pine, 30 ins. diam., brs. S. 52°W., 29 lks. dist., marked T 6 S R 32 E S 16 B.T. A pine, 24 ins. diam., brs. N. 56°W., 50 lks. dist., marked T 6 S R 32 E S 9 B T.
	Land; mountainous.
	Soil; 2nd rate.
	Densely covered with forests of pine, fir & tamarack tim- ber, 80 chs.
	E. on random line bet. Secs. 10 & 15
	Var. 20°E.
1.40	Ravine, course S.
7.00	Wagon road, course N.W. & S.E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
	Thence over gently rolling ground to