

Subdivisional Lines, T 6 S R 32 E W M.

|         |   |
|---------|---|
| Chains. | N. bet. Secs. 29 & 30.  |
|         | Var. 20° E.   |
|         | Ascend abruptly.  |
| 36.00   | Top of mountain, course E. & W.   |
| 40.00   | Set basalt stone, 18 x 10 x 6 ins., 12 ins. in ground, for<br>$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face; dug pits, 18 x 18 x 12<br>ins., N. & S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound<br>of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.   |
| 80.00   | To point, 100 ft. below $\frac{1}{4}$ Sec. Cor. and<br>Set basalt stone, 16 x 8 x 8 ins., 10 ins. in ground, for<br>Cor. to Secs. 19, 20, 29 & 30, marked with 2 notches<br>on S. and 5 notches on E. edges; dug pits, 18 x 18 x 12<br>ins. in each Sec., $5\frac{1}{2}$ ft. dist. and raised mound of<br>earth, 2 ft. high, $4\frac{1}{2}$ ft. base alongside. |
|         | Land; mountainous.  |
|         | Soil; 2nd rate.   |
|         | Scattering pine timber, 80 chs.   |
| <hr/>   |   |
|         | E. on random line bet. Secs. 20 & 29.   |
|         | Var. 19° E.   |
| 27.00   | Ravine, course S.E.   |
| 40.00   | To a point about 100 ft. below Sec. Cor. and set temp. $\frac{1}{4}$<br>Sec. Cor.   |
| 53.00   | Ravine, course S.   |
| 80.26   | Intersect N. & S. line at 20 lks. S. of Cor. to Secs. 20,<br>21, 28 & 29.   |
|         | Thence I run  |
|         | S. 89° 51' W. on true line bet. Secs. 20 & 29.  |
|         | With same Var.  |
| 40.13   | Set basalt stone, 16 x 10 x 5 ins., 10 ins. in ground, for<br>$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, and raised mound of<br>stone, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.   |
| 80.26   | The Cor. to Secs. 19, 20, 29 & 30.  |
|         | Land; mostly sloping to S., mountainous & broken.   |
|         | Soil; rocky 3rd rate.   |
|         | Scattering pine timber, 80.26 chs.  |