

Exterior Lines, T.6 S., R.33 E., W. M.

Chains

Cor. to Secs. 5, 6, 31 & 32, marked with 5 notches on E. and 1 notch on W. edges, from which

A pine, 11 ins. diam., brs. N.44°E., 21 lks. dist., marked T 6 S R 33 E S 32 B T.

A pine, 30 ins. diam., brs. S.52°E., 39 lks. dist., marked T 7 S R 33 E S 5 B T.

A pine, 24 ins. diam., brs. S.50°W., 35 lks. dist., marked T 7 S R 33 E S 6 B T.

A pine, 30 ins. diam., brs. N.14°W., 50 lks. dist., marked T 6 S R 33 E S 31 B T.

Land; rolling.

Soil; 2nd rate.

Densely covered with forests of pine & fir, 76.17 chs.

S.89°46'E. on true line bet. Secs. 5 & 32.

Var. 19 $\frac{1}{2}$ °E.

Ascend.

17.00 Ravine, course S.

40.00 A point, 300 ft. above last Sec. Cor.

Set granite stone, 16 x 10 x 4 ins., 11 ins. in ground, for

$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which

A pine, 40 ins. diam., brs. N.68°W., 41 lks. dist., marked $\frac{1}{4}$ S B T.

A pine, 36 ins. diam., brs. S.36°E., 91 lks. dist., marked $\frac{1}{4}$ S B T.

61.00 Brook, 4 lks. wide, runs S.

80.00 Set granite stone, 16 x 13 x 12 ins., 11 ins. in ground, for

Cor. to Secs. 4, 5, 32 & 33, marked with 4 notches on E. and 2 notches on W. edges, from which

A pine, 10 ins. diam., brs. N.62°E., 55 lks. dist., marked T 6 S R 33 E S 33 B T.

A fir, 10 ins. diam., brs. S.60°E., 88 lks. dist., marked T 7 S R 33 E S 4 B T.

A fir, 10 ins. diam., brs. S.47°W., 15 lks. dist., marked T 7 S R 33 E S 5 B T.

A pine, 20 ins. diam., brs. N.15°W., 56 lks. dist.,