

Exterior Lines, T 6 S R 33 E W M.

Chains

A juniper, 10 ins. diam., brs. N.83°E., 75 lks. dist.,  
marked T 6 S R 34 E S 30 B.T.

A fir, 10 ins. diam., brs. S.42°E., 167 lks. dist.,  
marked T 6 S R 34 E S 31 B T.

A fir, 10 ins. diam., brs. S. 60°W., 148 lks. dist.,  
marked T 6 S R 33 E S 36 B T.

A fir, 24 ins. diam., brs. N.37½°W., 188 lks. dist.,  
marked T 6 S R 33 E S 25 B T.

Land; mountainous.

Soil; 3rd rate.

Densely covered with forests of pine, fir, spruce and tam-  
arack, 80 chs.

Thick undergrowth of black pine & spruce, 80 chs.

N. bet. Secs. 25 & 30.

Var.19°10'E.

Descend.

34.50 Trail, courses E. & W.

40.00 A point, 200 ft. below Sec. Cor.

Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for ¼  
Sec. Cor., marked ¼ S on W. face, from which

A spruce, 10 ins. diam., brs. N.74°E., 54 lks. dist.,  
marked ¼ S B T.

A spruce, 10 ins. diam., brs. S.85°W., 18 lks. dist.,  
marked ¼ S B T.

66.00 Brook, 3 lks. wide, runs N.E.

80.00 Set granite stone, 18 x 12 x 10 ins., 12 ins. in ground,  
for Cor. to Secs. 19, 24, 25 & 30, marked with 4 notches  
on N. and 2 notches on S. edges, from which

A pine, 8 ins. diam., brs. N.85°E., 77 lks. dist.,  
marked T 6 S R 34 E S 19 B T.

A pine, 12 ins. diam., brs. S.57°E., 52 lks. dist.,  
marked T 6 S R 34 E S 30 B T.

A pine, 10 ins. diam., brs. S.10°W., 57 lks. dist.,  
marked T 6 S R 33 E S 25 B T.

A tamarack, 10 ins. diam., brs. N.38°W., 71 lks. dist.,