

Subdivisional Lines, T. 6 S., R. 33 E., W. M.

Chains	
39.90	Set basalt stone, 15 x 9 x 6 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which A pine, 4 ins. diam., brs. N.50°E., 9 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 4 ins. diam., brs. S.43°E., 12 lks. dist., marked $\frac{1}{4}$ S B T.
79.80	The Cor. to Secs. 14, 15, 22 & 23. Land; hilly. Soil; 2nd rate. Densely covered with forests of tamarack & black pine tim- ber, 79.80 chs. Thick undergrowth of small pine & spruce, 79.90 chs. June 27, 1883.
N. bet. Secs. 14 & 15.	Var. 18°30'E.
Descend.	
32.20	Cable creek, 8 lks. wide, course N.W. Thence ascend along hillside, facing S.W.
40.00	Set basalt stone, 14 x 10 x 8 ins., 9 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which A pine, 8 ins. diam., brs. S.15°W., 18 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 10 ins. diam., brs. S.62°E., 14 lks. dist., marked $\frac{1}{4}$ S B T.
42.50	Marshy ravine, course W.
45.00	Ascend abruptly.
55.00	Top of ascent, course E. & W. Thence descend through burnt timber.
76.50	Spring runs N.W.
80.00	A pine, 18 ins. diam., which I marked T 6 S S 11 on N.E. R 33 E S 14 on S.E S 15 on S.W. and S 10 on N.W. faces, with 4 notches on S. and