

Subdivisional Lines, T 6 S R 33 E W M.

Chains

2 notches on E. edges, for Cor. to Secs. 10, 11, 14 & 15, from which

A pine, 10 ins. diam., brs. N.31°E., 6 lks. dist., marked T 6 S R 33 E S 11 B T.

A pine, 10 ins. diam., brs. S.14°E., 5 lks. dist., marked T 6 S R 33 E S 14 B T.

A pine, 8 ins. diam., brs. S.56°W., 32 lks. dist., marked T 6 S R 33 E S 15 B T.

A pine, 8 ins. diam., brs. N.66°W., 21 lks. dist., marked T 6 S R 33 E S 10 B T.

Land; hilly.

Soil; 2nd rate.

Densely covered with pine & tamarack timber, partly deadened by fire, 80 chs.

Thick undergrowth of small pine, 80 chs.

E. on random line bet. Secs. 11 & 14.

Var. 19°40'E.

Ascend hill, facing N.W.

20.00 Top of hill & descend gently.

40.00 Set temp. 1/4 Sec. Cor.

47.55 Spring branch, 4 lks. wide, course N.

79.60 Intersect N. & S. line at 30 lks. N. of Cor. to Secs. 11, 12, 13 & 14.

Thence I run

N.89°47'W. on true line bet. Secs. 11 & 14.

With same Var.

39.80 Set basalt stone, 10 x 10 x 8 ins., 7 ins. in ground, for 1/4 Sec. Cor., marked 1/4 on N. face, from which

A fir, 10 ins. diam., brs. N.64°E., 26 lks. dist., marked 1/4 S B T.

A fir, 11 ins. diam., brs. S.43°E., 3 lks. dist., marked 1/4 S B T.

79.60 The Cor. to Secs. 10, 11, 14 & 15.

Land; hilly. Soil; 2nd rate. Densely covered with forests of pine & fir timber, 79.60 chs.