

Subdivisional Lines, T 6 S R 33 E W M.

Chains	
77.00	Spring branch, 2 lks. wide, course N.W., at foot of descent.
79.90	Intersect N. & S. line at Cor. to Secs. 10, 11, 14 & 15.
	Thence I run
	W. on true line bet. Secs. 10 & 15.
	With same Var.
39.95	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
	for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face, from which
	A pine, 4 ins. diam., brs. S.62°E., 9 lks. dist.,
	marked $\frac{1}{4}$ S B T.
	A pine, 4 ins. diam., brs. N.40°W., 13 lks. dist.,
	marked $\frac{1}{4}$ S B T.
79.90	The Cor. to Secs. 9, 10, 15 & 16.
	Land; rolling.
	Soil; 2nd rate.
	Densely covered with forests of pine, fir, tamarack and
	spruce timber, 79.90 chs.
	Thick undergrowth of small pine, fir & tamarack, 79.90 chs.
	June 30, 1883.
	N. bet. Secs. 19 & 10.
	Var. 22°E.
5.00	Creek, 10 lks. wide, course N.W.
7.00	Trail, course E. & W.
15.00	Top of hill from creek.
40.00	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,
	for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which
	A pine, 6 ins. diam., brs. S.45°E., 6 lks. dist.,
	marked $\frac{1}{4}$ S B T.
	A fir, 8 ins. diam., brs. N.85°W., 7 lks. dist.,
	marked $\frac{1}{4}$ S B T.
69.00	Ravine, course N.W.
78.00	" " " N.E.
78.00	Foot of descent.
80.00	Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground,
	for Cor. to Secs. 3, 4, 9 & 10, marked
	T 6 S S 3 on N.E.