

## Exterior Lines, T 6 S R 34 E W M.

| Chains |   |
|--------|---|
|        | <p>A pine, 6 ins. diam., brs. N.45°W., 8 lks. dist.,<br/>marked T 6 S R 34 E S 31 B T.</p> <p>Land; rolling &amp; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, fir, tamarack and<br/>spruce, 76.02 chs.</p> <p>Thick undergrowth of small pine, fir, tamarack &amp; balm, 76.02<br/>chains.</p>   |
|        | <p>S.89°42'E. on true line bet. Secs. 5 &amp; 32.<br/>Var. 19°E.</p>  |
| 40.00  | <p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for <math>\frac{1}{4}</math><br/>Sec. Cor., marked <math>\frac{1}{4}</math> S on N. face, from which</p> <p>A tamarack, 10 ins. diam., brs. N.45°E., 14 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p> <p>A tamarack, 11 ins. diam., brs. S.40°E., 20 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p>  |
| 80.00  | <p>A tamarack, 8 ins. diam., which I mark</p> <p>T 6 S S 33 on N.E.<br/>R 34 E S 4 on S.E.<br/>T 7 S S 5 on S.W. and<br/>S 32 on N.W. faces, with<br/>4 notches on E. and<br/>2 notches on W. sides,<br/>from which</p> <p>A tamarack, 12 ins. diam., brs. N.36°E., 8 lks. dist.,<br/>marked T 6 S R 34 E S 33 B T.</p> <p>A tamarack, 18 ins. diam., brs. S.6°E., 18 lks. dist.,<br/>marked T 7 S R 34 E S 4 B T.</p> <p>A tamarack, 10 ins. diam., brs. S.54°W., 12 lks. dist.,<br/>marked T 7 S R 34 E S 5 B T.</p> <p>A fir, 8 ins. diam., brs. N.18°W., 12 lks. dist.,<br/>marked T 6 S R 34 E S 32 B T.</p> |
|        | <p>Land; rolling.</p> <p>Soil; 2nd rate. Densely covered with pine, fir, tamarack<br/>and spruce, 80 chs.</p>   |