

Exterior Lines, T 6 S R 34 E W M.

Chains

S.89°42'E. on true line bet. Secs. 4 & 33.

Var.19°E.

18.50 Creek, 15 lks. wide, runs S.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$

Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which

A pine, 9 ins. diam., brs. N.69°W., 20 lks. dist.,
marked $\frac{1}{4}$ S B T.

A pine, 8 ins. diam., brs. S.79°E., 16 lks. dist.,
marked $\frac{1}{4}$ S B T.

49.65 Spring branch, course N.

80.00 A pine, 10 ins. diam., which I marked

T 6 S S 34 on N.E.

R 34 E S 3 on S.E.

T 7 S S 4 on S.W. and

S 33 on N.W. faces, with

3 notches on E. & W. sides,

from which

A pine, 6 ins. diam., brs. N.42°E., 30 lks. dist.,
marked T 6 S R 34 E S 34 B T.

A pine, 6 ins. diam., brs. S.39°E., 21 lks. dist.,
marked T 7 S R 34 E S 3 B T.

A spruce, 18 ins. diam., brs. S.65°W., 20 lks. dist.,
marked T 7 S R 34 E S 4 B T.

A spruce, 15 ins. diam., brs. N.37°W., 29 lks. dist.,
marked T 6 S R 34 E S 33 B T.

Land; rolling.

Soil; 2nd rate.

Densely covered with forests of pine, tamarack & fir, 80 chs.

Thick undergrowth of balm & huckleberry, 80 chs.

S.89°42'E. on true line bet. Secs. 3 & 34.

Var.19°E.

12.00 Creek, 5 lks. wide, runs N.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$

Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which