

Exterior Lines, T 6 S R 34 E W M.

Chains

2 notches on S. edges; from which

A pine, 10 ins. diam., brs. N.41°E., 14 lks. dist.,
marked T 6 S R 35 E S 19 B T.

A pine, 10 ins. diam., brs. S.24°E., 20 lks. dist.,
marked T 6 S R 35 E S 30 B T.

A pine, 10 ins. diam., brs. S.83°W., 5 lks. dist.,
marked T 6 S R 34 E S 25 B.T.

A pine, 10 ins. diam., brs. N.33°W., 23 lks. dist.,
marked T 6 S R 34 E S 24 B T.

Land; high & rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir, tamarack & spruce,
80 chs.

N. bet. Secs. 19 & 24.

Var. 20°E.

6.40 Creek, 8 lks. wide, runs W. Ascend.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$

Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which

A pine, 12 ins. diam., brs. S.30°E., 45 lks; dist.,
marked $\frac{1}{4}$ S B T.

A pine, 10 ins. diam., brs. S.18°W., 53 lks. dist.,
marked $\frac{1}{4}$ S B T.

46.00 Top of mountain, about 600 ft. above creek, course E. & W.
over rolling ground.

57.00 Descend.

80.00 A point, about 300 ft. below top of mountain.

Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for

Cor. to Secs. 13, 18, 19 & 24, marked

T 6 S S 18 on N.E.

R 35 E S 19 on S.E.

R 34 E S 24 on S.W. and

S 13 on N.W. faces, with

3 notches on N. & S. edges;

from which