

## Exterior Lines, T 6 S R 34 E W M.

| Chains |  |
|--------|--|
|        | <p>A pine, 24 ins. diam., brs. N.54°E., 20 lks. dist.,<br/>marked T 6 S R 35 E S 18 B T.</p> <p>A pine, 8 ins. diam., brs. S.66°E., 20 lks. dist.,<br/>marked T 6 S R 35 E S 19 B T.</p> <p>A pine, 10 ins. diam., brs. S.32°W., 31 lks. dist.,<br/>marked T 6 S R 34 E S 24 B T.</p> <p>A spruce, 10 ins. diam., brs. N.9°W., 32 lks. dist.,<br/>marked T 6 S R 34 E S 13 B T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forests of pine, spruce, fir &amp; tamarack, 80 chs.</p> <p>Thick undergrowth of balm, small pine &amp; fir, 80 chs.</p> <p style="text-align: right;">July 16, 1883.</p> |
|        | <p>N. bet. Secs. 13 &amp; 18.</p> <p style="text-align: right;">Var. 19°30'E.</p>  |
| 5.00   | <p>Brook, 4 lks. wide, runs W.</p> <p>Ascend.</p>  |
| 39.50  | <p>Brook, 2 lks. wide, runs N.W.</p>   |
| 40.00  | <p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S on W. face; from which</p> <p>A pine, 10 ins. diam., brs. S.29°W., 26 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p> <p>A pine, 10 ins. diam., brs. N.15°E., 9 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S B T.</p>  |
| 59.00  | <p>Top of mountain, 500 ft. above last Sec. Cor., enter table lands.</p>   |
| 80.00  | <p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 7, 18, 13 &amp; 12, marked</p> <p style="text-align: center;">T 6 S S 7 on N.E.<br/>R 35 E S 18 on S.E.<br/>R 34 E S 13 on S.W. and<br/>S 12 on N.W. faces, with<br/>2 notches on N. &amp; 4 on S. edges;</p>  |