

Subdivisional Lines, T 6 S R 34 E W M.

Chains

markes  $\frac{1}{4}$  S B T.

62.05 Intersect 1st Standard Parallel S. at point 27.75 chs. W. of Cor. to Secs. 32 & 33, T 5 S R 34 E., at which point  
I

Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 1 & 2; marked

C C T 6 S R 34 E on S.

S 1 on E. & S 2 on W. faces,

with 1 notch on E. and

5 notches on W. edges;

from which

A fir, 5 ins. diam., brs. S.60°W., 24 lks. dist., marked T 6 S R 34 E S 2 B T.

A pine, 8 ins. diam., brs. S.73°E., 18 lks. dist., marked T 6 S R 34 E S 1 B T.

Land; rolling.

Soil; 2nd rate.

Densely covered with forests of pine, fir & spruce, 62.05 chs.

July 22, 1883.

From the Cor. to Secs. 2, 3, 34 & 35 on S. Bdy. of Tp., which is a basalt stone, 16 x 10 x 10 ins., firmly set in ground, marked with 2 notches on E. and 4 notches on W. edges; from which

A pine, 30 ins. diam., brs. N.79°E., 156 lks. dist., marked T 6 S R 34 E S 35 B T.

A pine, 18 ins. diam., brs. S.79°E., 126 lks. dist., marked T 7 S R 34 E S 2 B T.

A pine, 30 ins. diam., brs. S.63°W., 157 lks. dist., marked T 7 S R 34 E S 3 B T.

A pine, 36 ins. diam., brs. N.68°W., 180 lks. dist., marked T 6 S R 34 E S 34 B.T.

I run

N. bet. Secs. 34 & 35.