

Subdivisional Lines, T 6 S R 34 E W M.

Chains

Var. 19°40'E.

Ascend hill, course E. & W.

28.00 Top of hill, course E. & W.

30.00 Descend gradually.

40.00 Set spruce post, 3 ft. long, 3 ins. sq., 24 ins. in ground

for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  S. on W. face; from which

A spruce, 18 ins. diam., brs. S. 60°W., 12 lks. dist.,

marked  $\frac{1}{4}$  S B T.

A fir, 18 ins. diam., brs. N. 75°E., 35 lks. dist.,

marked  $\frac{1}{4}$  S B T.

69.50 Ravine, course N.W.

80.00 Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground,

marked

T 6 S S 26 on N.E.

R 34 E S 35 on S.E.

S 34 on S.W. and

S 27 on N.W. faces, with

1 notch on S. and

2 notches on E. edges;

from which

A pine, 6 ins. diam., brs. N. 30°E., 15 lks. dist.,

marked T 6 S R 34 E S 26 B T.

A pine, 10 ins. diam., brs. S. 44°E., 36 lks. dist.,

marked T 6 S R 34 E S 35 B T.

A pine, 8 ins. diam., brs. S. 55°W., 27 lks. dist.,

marked T 6 S R 34 E S 34 B T.

A pine, 10 ins. diam., brs. N. 70°W., 26 lks. dist.,

marked T 6 S R 34 E S 27 B T.

Land; hilly.

Soil; 2nd rate.

Densely covered with forests of pine, fir, spruce & tamarack, 80 chs.

Thick undergrowth of spruce & pine, 80 chs.

E. on random line bet. Secs. 26 & 35.

Var. 19°30'E.