

Subdivisional Lines, T 6 S R 34 E W M.

Chains	
	W. on true line bet. Secs. 10 & 15.
	With same Var.
40.00	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which A spruce, 6 ins. diam., brs. S.18°E., 12 lks. dist., marked $\frac{1}{4}$ S B T. A spruce, 8 ins. diam., brs. N.24°W., 9 lks. dist., marked $\frac{1}{4}$ S B T.
80.00	The Cor. to Secs. 9, 10, 15 & 16. Land; rolling on E. $\frac{1}{2}$, remainder level table land. Soil; 2nd rate. Densely covered with forests of pine, fir & spruce, 80 chs. July 27th 1883.
	N. bet. Secs. 9 & 10.
	Var. 20°E.
	Over rolling ground through dense forests.
38.00	Trail, course N.E. & S.W.
40.00	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which A pine, 9 ins. diam., brs. S.88°W., 9 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 10 ins. diam., brs. N.74°E., 7 lks. dist., marked $\frac{1}{4}$ S B T.
55.00	Descend hill, course N.E. & S.W.
70.00	Foot of hill, ravine, course N.W.
80.00	Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 3, 4, 9 & 10, marked T 6 S S 3 on N.E. R 34 E S 10 on S.E. S 9 on S.W. and S 4 on N.W. faces, with 5 notches on S. and 3 notches on E. edges; from which