

Subdivisional Lines, T 6 S R 34 E W M.

Chains	Densely covered with forests of pine & fir, 79.95 chs. Thick undergrowth of balm, huckleberry & small pine, 79.95 chs.
	N. bet. Secs. 3 & 4. Var. 19°40'E. Over rolling ground.
18.00	Ravine, course W.
40.00	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which A fir, 12 ins. diam., brs. N. 61°W., 33 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 24 ins. diam. brs. S. 80°E., 105 lks. dist., marked $\frac{1}{4}$ S B T.
	Ascend.
61.30	Intersect the 1st Standard Parallel S. at point 27.47 chs. W. of Cor. to T 5 S Rs 33 $\frac{1}{2}$ & 34 E., at which point, I Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 3 & 4, marked C C T 6 S R 34 E on S. S 3 on E. & S 4 on W. faces, with 3 notches on E. & W. edges; from which A fir, 10 ins. diam., brs. S. 80°E., 5 lks. dist., marked T 6 S R 34 E S 3 B T. A fir, 8 ins. diam., brs. S. 8°W., 45 lks. dist., marked T 6 S R 34 E S 4 B T.
	Land; rolling. Soil; 2 nd rate. Densely covered with forests of pine, fir, tamarack and spruce, 61.30 chs. Thick undergrowth of small pine, 61.30 chs.
	From the Cor. to Secs. 4, 5, 32 & 33 on S. Bdy. of Tp., which is a tamarack, 8 ins. diam., marked