

Subdivisional Lines, T 6 S R 34 E W M.

Chains	
	N. bet. Secs. 28 & 29.
	Var. 19°30'E.
	Over rolling ground.
14.00	Creek, 8 lks. wide, course S.W.
32.00	Top of small hill, from creek.
40.00	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face; from which A pine, 8 ins. diam., brs. W. 5 lks. dist., marked $\frac{1}{4}$ S B T. A pine, 8 ins. diam., brs. S. 86°E., 18 lks. dist., marked $\frac{1}{4}$ S B T.
56.25	Spring branch, 4 lks. wide, course E.
75.15	" " 2 " " , runs E. Thence ascend to
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 20, 21, 28 & 29, marked T 6 S S 21 on N.E. R 34 E S 28 on S.E. S 29 on S.W. and S 20 on N.W. faces, with 2 notches on S. and 4 notches on E. edges; from which A pine, 10 ins. diam., brs. N. 68°E., 37 lks. dist., marked T 6 S R 34 E S 21 B T. A pine, 10 ins. diam., brs. S. 39°E., 34 lks. dist., marked T 6 S R 34 E S 28 B T. A tamarack, 27 ins. diam., brs. S. 59°W., 132 lks. dist., marked T 6 S R 34 E S 29 B T. A tamarack, 13 ins. diam., brs. N. 50°W., 52 lks. dist., marked T 6 S R 34 E S 20 B T.
	Land; gently rolling.
	Soil; good 2nd rate.
	Densely covered with forests of pine, fir, tamarack & spruce mostly deadened by fires, 80 chs.