

Subdivisional Lines, T 6 S R 34 E W M.

Chains

N. bet. Secs. 4 & 5.

Var. 20°E.

Descending.

40.00 Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground,  
for  $\frac{1}{4}$  Sec. Cor., marked  $\frac{1}{4}$  S on W. face; from which  
A pine, 8 ins. diam., brs. S. 73°E., 29 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

A tamarack, 10 ins. diam., brs. N. 80°W., 24 lks. dist.,  
marked  $\frac{1}{4}$  S B T.

52.00 Enter flat at foot of hill.

60.70 Intersect the 1st Standard Parallel S. at a point, 27.78  
chs. W. of Cor. to Secs. 35 & 36, T 5 S R 33 $\frac{1}{2}$  E., at  
which point, I

Set pine post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for  
for Closing Cor. to Secs. 4 & 5, marked

C C T 6 S R 34 E on S.

S 4 on E. and

S 5 on W. faces, with

4 notches on E. and

2 notches on W. edges;

from which

A pine, 9 ins. diam., brs. S. 71°W., dist.,

marked T 6 S R 34 E S 5 B T.

A pine, 9 ins. diam., brs. S. 41°E., dist.,

marked T 6 S R 34 E S 4 B T.

Land; hillside facing N.

Soil; 2nd rate.

Densely covered with forests of pine, tamarack & spruce,  
60.70 chs.

Thick undergrowth of small pine, 60.70 chs.

From the Cor. to Secs. 5, 6, 31 & 32 on S. Bdy. of Tp.,  
which is post, 4 ins. sq., firmly set in ground, marked

T 6 S S 32 on N.E.

R 34 E S 5 on S.E.