

J. M. Pruett

Course	Degree	Minutes	Chains	Links
West	70	00		
	80			
West	40	00		
West	80	37 1/2		

Remains July 2nd 1882
J. H. Kelley

To Subdivide Sec 6 T34N R32E
 I went to 1/4 Post on East line of Said Sec 6
 found said post with charcoal in mound - pits etc
 positive evidence of Gov. work from which I
 set temp 1/4 post in center of Sec -
 to 1/4 post on West line of Said Sec 6 found
 charcoal in mound with pits etc positive
 evidence of Gov. work from said
 corner I went to the 1/4 post on the south
 side of said sec found charcoal in mound
 with pits all defined from which I ran
 north
 I set temp post on line running E + W + Rv
 to 1/4 post on the North line of said sec 6
 found Mound with coal + pits positive evidence
 of Gov. work from which I returned to the
 center of Said Sec 6 and set permanent interior
 1/4 post at the intersection of the E + W + N + S lines
 thus leaving all fractions on the West + North of Said sec

I hereby certify that the above are
 the true notes taken by me assisted by W. M. Hume
 at request of J. M. Pruett

J. H. Riley
 C. Surveyor