

## PLAT AND RECORD OF SURVEY No. 7619

Samuel Roe

After qualifying  
 E. H. Berry and  
 L. W. Berry as Chainmen and  
 F. C. Mord and Wm Brown as  
 Flaymen

We proceeded to Survey out the  
 following described Land to wit;  
 the South East  $\frac{1}{4}$  of section 14  
 T5 N R 35 E of W. Va.

Commencing at the Standard corner  
 of the 1<sup>st</sup> Standard Parcell North  
 between secs 35 & 36. T5 N R 35 E  
 and run Va.  $21^{\circ}$  E.

Three miles

Thence commencing at the corner of  
 sec 13 & 24 on East boundary of Town  
 5. N. R. 35 E. from we we  
 run Va.  $21^{\circ}$  E.

West 40 25  $\frac{1}{4}$  sec post

" 80 50 Road

Thence commencing at the  $\frac{1}{4}$  sec post  
 between secs 15 & 22. we  
 run

West 40 00 found sec post on hill side for  
 Secs 14, 15, 22 & 23 Thence

" 9 94 dry creek

" 40 00 found  $\frac{1}{4}$  sec post on the ground  
 " 80 75 Road at which point I  
 planted a post  $6\frac{1}{4}$  in with a  
 glass bottle at the bottom of  
 the pit pained around and dug  
 pits for S. E. corner

Course.	Degrees.	Minutes.	Chains.	Links.	
West			40	37	from said corner we run S 74° a post and planted a Stone 20 x 6 x 8 with a Glass bottle at the bottom of said pit raised mound and dug pits for S.W. corner we returned to S.E. corner and run <i>1/2</i> <i>1/2</i> <i>21° E.</i>
North			84	00	and found post and mound said post and mound was established by Sherron & party Surveyor I returned and established a corner for N. E. corner at
"			40	75	by planting a post 4 x 6 in with a glass bottle at the bottom of post for N.E. corner from wh we run
West			35	00	and intersect a line run from 1/4 sec post on north boundary of sec 14 to 1/4 post on south boundary of sec 14 at which point I planted a post 4 in square with a glass bottle at bottom of post raised mound dug pits for the S.W. corner

South 83 on West

I hereby certify that the above  
is a true and correct survey  
and subdivision of said section

A. L. Coffey  
County Surveyor  
for 26<sup>th</sup> 1887