

PLAT AND RECORD OF SURVEY No. 7119
 Survey for John G. Thompson Mar 10th 1883

Course. Degree. Minutes. Chains. Links.

Subdivision of Sec. 8 T. 3. N. 30. in order to run

off the E¹/₂ of NW¹/₄ and W¹/₂ of NE¹/₄ and E¹/₂ of SW¹/₄ and W¹/₂ of SE¹/₄ of
 sec 8 T. 3. N. 30. Sverro Chaimman { J. E. Parsons
 G. C. Parsons



Begin at the N. W. corner of sec 8 after removing
 the original ^{corner} by rebuilding mound and run on true line

East	20 00	set temporary point
	39 88	came upon original ¹ / ₄ S marked by rock & old stake
	59 82	set temp stake
	79 76	In ploughed field and section corner destroyed Thence on random line
South	39 88	intersect ¹ / ₄ sec line 15 links W of original ¹ / ₄ S
	79 76	set temp stake. No signs of old corner could be found. I next go to the S. W. cor of sec 8 and renew original corner by setting Rock 9x9x16" with Porcelain under it. Thence on random line
East	20 00	set temp stake
	40 00	" " " in ploughed field and old corner destroyed
	60 00	" " "
	79 68	set stake for ^{S. E.} cor of sec. 39.88 chs south of original ¹ / ₄ S below sections 849. The distances on the North and South sides of this section are made to agree with the standard of measure afforded by the distance betwe-

PLAT AND RECORD OF SURVEY No. 7119

Links

the government corners at the N.W. cor of sec 8 and the N $\frac{1}{4}$ S. I neither reestablish nor renew with permanent monuments the corners on the east side of sec 8 because the owners of the field seem disposed to plough them up. I therefore set corners on the south and north sides of section as follows

Beginning at the point established at the S.E. cor of sec 8 run on true line

- West
- 19 92 set rock 7"x10"x14"
- 39 84 " " 6"x9"x18" with porcelain underneath for $\frac{1}{4}$ S. cor
- 59 76 " " 5"x7"x16" over bottle with the number 43 on the bottom of it.
- 79 68 S.W. cor of sec 8

Beginning at the N $\frac{1}{4}$ S. cor of sec 8 at established point run on true line

- West
- 17 94 set Rock 6"x7"x12" with a cuttin de Bourbon bottle underneath
- 39 88 Rock set at the original quarter corner
- 59 82 set rock 7"x10"x25" with porcelain underneath
- 79 76 N.W. cor of sec 8

From the N $\frac{1}{4}$ S. I run on direct line to south $\frac{1}{4}$ S

- South
- 40 00 set temp post for line point
- From E $\frac{1}{4}$ S. Run on random West
- West
- 20 00 set temp stake
- 40 12 cross north and south quarter sec line make temp point
- 60 00 temp stake
- 79 70 intersect sec line 29 lbs south of $\frac{1}{4}$ S. cor which I name by setting rock 6"x9"x14" with glass underneath it.

Thence on true line

- East
- 19 79 set rock 18 lbs N of temp stake
- 39 58 Drive King Bolt by bottle 12 lbs N of temp post at intersection of lines.
- 59 64 set rock 33 lbs over bottle with figure 11 on the bottom of it

I certify the foregoing field notes and plat showing subdivision of sec 8 T. 2 S. R. 30 to be true

P. Zahner Dept Co Surveyor